

Minutes of Pre-bid Meeting held on 20/12/2016 for Poultry Shed

Part of BOQ at S. No 1 for earthwork (Civil component) may be read as under and the rate may be quoted accordingly. Poultry shed

| Sr. No. | Particular | Quantity | Unit | Rate | Amount |
|---------|---|----------|------|------|--------|
| 1 | Earthwork : Excavation in foundation trenches or drains not exceeding 1.5m in width and 60cm in depth or 10sqm on plan including dressing of sides and ramming of bottoms lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50m. (For all kind of soils including hard rock) Filling available excavated earth (excluding rock in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50m and lift up to 1.5m. cum | 3.84 | cum | | |